

**MISCELLANEOUS CIVIL WORKS IN NIPFP CAMPUS AT 18/2
SATSANG MARG, SPECIAL INSTITUTIONAL AREA
NEW DELHI- 110067.**

**FOR
NATIONAL INSTITUTE OF PUBLIC FINANCE & POLICY.
(NIPFP)**



**PART-A
(FINANCIAL BID)**

SPECIFICATIONS DOCUMENTS :

Architects M/s

SPACE ACE

**ARCHITECTS & INTERIOR DESIGNERS
V-20A/05 DLF CITY-III, GURGAON,
HARYANA - 122002
TEL. PH. No. :- 0124-4106618
Email: spaceace.india@gmail.com**

Dated:06/06/2019

SCHEDULE OF QUANTITIES					
Miscellaneous Civil works in NIPFP Campus					
SECTION-1 : CIVIL WORK					
Item No.	Description of Item	Quantity	Unit	Rate Rs.	Amount Rs.
1	Providing & Fixing Dholpur Stone 40mm Thick over 12 mm thick layer of cement mortar 1:3 (1 cement & 3 course sand) up to the height of 40 ft on the exterior of the brick wall after the cleaning of surface and properly aligning including cost of scaffolding at all heights etc complete with clamps (if required) & fastners (cost of fasteners to be excluded in this item).	12	sq.m.		
2	Repairing and re fixing of Dholpur stone which have become loose and required repairing on the surface of the wall up to all heights by carefully removing and re fixing the same after cleaning of surface with 12 mm cement mortar 1:3 ratio (1 Cement & 3 Course sand) complete with curing including cost of scaffolding at all heights and clamps (if required) & fastners (cost of fasteners to be excluded in this item).	28	sq.m.		
3	Providing and Fixing expandable fasteners with threaded dia 10 mm with necessary plastic sleeves and galvanised M.S. screws including drilling holes in masonry work / CC / R.C.C. and making good etc. complete: 100mm long (S.S. Grade 304) the same should be dipped with bitumen solution (paint)	8000	Nos.		
4	Providing and placing 40mm thick kota stone on the road side drains or elsewhere including sealing of joints with cement mortar 1:2 complete in all respect.	27	sq.m.		
5	Providing and Fixing 40 mm Dia 20 GI , 2'0" to 2'6" Long MS pipe (24-30 inch long) encased with cement mortar 1:2 to be fixed with the chajjas, balcony & as a rain water pipes complete in all aspects up to satisfaction of architect.	140	Nos.		
TOTAL AMOUNT					
DISCOUNT (IF ANY)					
FINAL AMOUNT (INCLUDING GST)					